

SCHOOL DISTRICT OF PHILADELPHIA



Asbestos Hazard Emergency Response Act “AHERA”

THREE-YEAR RE-INSPECTION 2015-2016 and ASBESTOS MANAGEMENT PLAN for the

**Big Picture High School
El Centro de Estudiantes
ULCS# 5330
Building # B533001-1
136 Dauphin Street
Philadelphia, Pennsylvania 19133**

Year Built: 1909

November 2015

Conducted By:

Accredited Environmental Technologies, Incorporated
Batta Environmental Associates, Incorporated
Criterion Laboratories, Incorporated
Environmental Testing Consultants, LLC
G & C Environmental Services, Incorporated
KEM Partners, Incorporated
Synertech, Inc.
TTI Environmental, Inc.
USA Environmental Management, Inc.
The Vertex Companies, Inc.

Management Plan Prepared By:

Criterion Labs, Inc and Synertech Inc.

This report must remain in the Main Office as mandated by the US EPA AHERA Regulations.

AHERA THREE-YEAR REINSPECTION VOLUME IX

Table of Contents

Transmittal Letter

Executive Summary

- I. Summary list of Confirmed Asbestos Containing Building Materials
- II. Summary list of Assumed Asbestos Contain Building Materials
- III. Summary list of Non-Asbestos Containing Building Materials
- IV. Summary list of Non Suspect Asbestos Containing Building Materials
- V. Summary List of Auditorium DATA for this location
- VI. Summary list of Attic and/or Crawlspace DATA for this location
- VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

Section I Report of Re-Inspection

- A. Introduction
- B. Three-Year Re-inspection IX Overview
- C. Post- Management Plan Activities and Changes
 - C.1 - Sampling and Analysis
 - C.2 - New Floor Tile Sampling
 - C.3 - Abatement Activity
 - C.4 - Periodic (Six-Month) Surveillance (Damaged Materials)

Section II Re-Inspection Data

- A. Introduction
- B. Re-Inspection Key Definitions
- C. Room by Room Location Log Report

Section III Certificates

- A. Management Planner/Building Inspector Certificates

Section IV	Cross Reference Table	Page 1-8
	Asbestos Management Program	Page 9-19

SCHOOL DISTRICT OF PHILADELPHIA
EDUCATIONAL CENTER
440 NORTH BROAD STREET
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

January 2016


TO: All Principals
All Building Administrators

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: AHERA Three (3) Year Re-inspection IX report

In order to comply with the provisions of the Asbestos Hazard Emergency Response Act (AHERA) the attached report is submitted to you. The law requires that this report be kept in the Main/Principal's office. It cannot be removed from these locations. *If the school (program) is relocated to a different building, these environmental documents are to be safely retained for the next school/building occupants.* All asbestos reports must be available to the public and Federal EPA upon request.



Fran Burns
Chief Operation Officer



Francine Locke, M.S., Director
Office of Environmental Management
and Services

Executive Summary

This Asbestos Hazard Emergency Response Act (AHERA) Three-Year Re-inspection “Volume # IX” Management Plan at this location, has been completed and the report of re-inspection submitted to the School District of Philadelphia. The re-inspections in all School District of Philadelphia buildings of 2015-2016 were conducted and completed between October 5th, 2015 through March 30th, 2016 as a joint project by Accredited Environmental Technologies, Inc., Batta Environmental Associates, Inc., Criterion Laboratories, Inc., Environmental Testing Consultants, LLC, G & C Environmental Services, Inc., KEM Partners, Inc., Synertech, Inc., TTI Environmental, Inc., USA Environmental Management, Inc. and The Vertex Companies, Inc.

In general, the School District of Philadelphia Office of Environmental Management and Services conducts Environmental Impact Evaluations and provides Asbestos Inspection Reports prior to any renovation, demolition and/or maintenance activities. The AHERA report must be reviewed prior to any renovation, demolition and/or maintenance activities in order to avoid the unknowing disturbance to Asbestos Containing Building Materials identified within this location. In addition, prior to work activities above all drop ceilings this report should be reviewed to avoid potential disturbances to Asbestos Containing Materials. Refer to Section IV of the Cross Reference Table, for additional Asbestos Management Program information. Contact the Office of Environmental Management and Services to have an Environmental Impact Evaluation conducted prior to any renovation, demolition and/or maintenance activities within this facility.

The information contained in this report was obtained from the original Asbestos Management Plan for the school, from update reports on changes and activities since the completion of the 1st Management Plan for each location and from all prior inspections performed and documented in Volume # I through Volume VIII (dated respectively 1992, 1995, 1998, 2001, 2004, 2007, 2010 or 2013) (if applicable) - and by this Three-Year Re-inspection of this school. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and/or Monique Causley, of Synertech Inc.

The 2015-2016 inspection process included the addition of a comprehensive Room by Room Inventory of all Thermal (T), Surfacing (S) and Miscellaneous (M) Materials specific to each room of this facility. Inspections of each room's thermal, ceilings, walls, floors and miscellaneous items regardless of Asbestos Content are categorized on the Room by Room Location Log Report for this location. Rooms or areas of the facility that were not accessible at the time of the inspection are marked with an "X". The Room by Room Location Log Report is found in Section II C of this Management Plan.

All Presumed or Suspect Asbestos Containing Building Materials (ACBMs), listed in the following summary charts are categorized as Confirmed, Assumed, Non-Asbestos, and/or Non-Suspect (ACBMs) were identified in the original Management Plan, or in the Volume I through Volume VIII AHERA Three-Year Re-inspection reports, and were re-inspected as part of this project.

As mandated by the U S EPA AHERA regulations, periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Please feel free to contact the School District of Philadelphia's Office of Environmental Management and Services (OEMS) regarding any comments, questions, or concerns regarding this report or any Environmental related topic. OEMS staff can be reached at (215) 400 4750, via fax at (215) 400 4751 or via e-mail at flocke@philasd.org and/or gfjunod@philasd.org.

Additional information can be found on our website. Here is the link to the OEMS website.
<http://webgui.phila.k12.pa.us/offices/e/environmental>

I. Summary list of Confirmed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has CONFIRMED the presence of Asbestos. Contact OEMS prior to the disturbance of any of the following materials.*

Confirmed Asbestos Containing Building Materials for this location

Floor Tile VAT 9" x 9"	Pipe Fitting Insulation	Pipe Insulation > 6 inch
Pipe Insulation 2-6 inch	Plaster Ceiling	

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

II. Summary list of Assumed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials have not been sampled and should not be disturbed until verification of Asbestos Content. Contact OEMS for assessment and sampling prior to the disturbance of these materials.

Assumed Asbestos Containing Building Materials for this location

Floor Tile VAT 12" x 12"	Linoleum	Linoleum Sills
Pipe Fitting Insulation	Plaster Ceiling	Sheetrock Wall
Transite Stalls	Transite Urinal Covers	Transite Wall Panels
Transite Walls	Vibration Damper Cloth	Window Glaze

* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

** *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

III. Summary list of Non-Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has indicated NO Asbestos present or NO ASBESTOS DETECTED (NAD).*

Non- Asbestos Containing Building Materials for this location

Boiler Breeching	Plaster Walls
------------------	---------------

* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

** *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

IV. Summary list of Non-Suspect Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials are not typically known to contain Asbestos.

Non-Suspect Asbestos Containing Building Materials for this location

Brick Floor	Brick Wall	Ceiling Tile 2' x 4'
Cement Floor	Ceramic Tile Walls	Concrete Block Wall
Concrete Ceiling	Fiberglass Pipe Insulation	Partition Room Dividers
Wall Paper	Wood Floor	

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

V. Summary list of Auditorium DATA for this location

These charts are to be used for a quick reference of the Auditorium DATA within this facility. Sampling of the Auditorium Ceilings throughout the District is more difficult because of the various ceiling heights. As sampling occurs this information is updated on a case by case basis for each specific location and facility.

This is a list of known sampling information for this locations Auditorium

No Auditorium exists at this location.

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

VI. Summary list of Attic and/or Crawlspace DATA for this location

These charts are to be used for a quick reference regarding the Attics and/or Crawlspaces inspection DATA within this facility. Contact OEMS prior to entering any attic or crawlspace within this facility and refer to the below chart and legend for Category Rank determination. The Data relative to these spaces is updated as conditions change regarding Abatement or Renovation activity on a case by case basis for each specific location and facility. In general, Crawlspaces are below the basement or 1st floor and Attics are above the floor space.

Category Rank Legend

"A" - No Asbestos Containing Materials - Sample Results indicate NO ACM on pipes, fittings, elbows, or equipment located within this functional space, and NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection.
"B" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, HOWEVER, NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection.
"C" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, and LOCALIZED VISIBLE DEBRIS or DAMAGE observed at time of this inspection.
"D" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space and DISTRIBUTED VISIBLE DEBRIS or SIGNIFICANT DAMAGE observed at time of this inspection.
"E" - No Bulk Sample Results Available SUSPECT ACM OBSERVED. Contact OEMS immediately for additional instructions.

Attic/Crawlspace	Access Area	Floor Surface	Category Rank	Comments
Attic	X	X	X	Needs to be assessed
Crawlspace	X	X	X	Needs to be assessed

VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

These charts are to be used for a quick reference regarding the information known about the Pipe Chases and/or Pipe Shafts inspection DATA within this facility. Contact OEMS prior to performing renovation activities any Pipe Chase and/or Pipe Shaft within this facility and refer to the below chart and legend for Asbestos Content of various materials identified within each space. The Data relative to these spaces is updated as conditions change regarding Inspection, Abatement and/or Renovation activity on a case by case basis for each specific location and facility. In general, Pipe Chases are horizontal spaces and Pipe Shafts are vertical spaces.

Pipe Chases and Pipe Shafts need to be assessed.

Section I Report of Re-inspection

A. Introduction

B. Three-Year Re-inspection IX Overview

C. Post-Management Plan Activities and Changes

Section I - A

Report of Re-inspection

Introduction

The Three-Year Re-inspection IX was performed to fulfill the requirements of 40 CFR Part 763 - the Asbestos Hazard Emergency Response Act (AHERA). As required by AHERA, each Local Education Agency (LEA) must re-inspect all known confirmed or assumed Asbestos Containing Building Material (ACBM) located in the LEA's facilities. This re-inspection is intended to update the original Asbestos Management Plan for the LEA's facilities.

Multiple Building Inspectors of several firms performed the 2015/2016 re-inspection. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and Monique Causley, of Synertech Inc.

All of the certificates can be found in Section III.

During the re-inspection of each School District of Philadelphia facility, all of the Management Plans for that facility were reviewed. Information from the conclusions section of that report is included in this report. Additionally, information on activities such as abatements, cleanings, sampling and inspections, which have taken place since the completion of the original Management Plan, were reviewed during the re-inspection. Information on those activities is included in this report.

As mandated by the U S EPA AHERA regulations, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Section I - B

Three-Year Re-inspection IX Overview

Each homogeneous area of Asbestos Containing Building Material (ACBM) listed in the original Management Plan or in the 1992, 1995, 1998, 2001, etc., Three-Year Re-inspection reports were inspected for the AHERA Three-Year Re-inspection Volume IX, and the information for that material verified. Any changes to a homogeneous area listed in the updates to the Management Plans were verified. Any area of suspected ACBM found in the course of the re-inspection, and not listed in the Management Plan or updates, were either assumed to contain asbestos or sampled and analyzed to determine their asbestos content. Any such new areas either assumed to contain asbestos or determined through analysis to contain asbestos were included in the report of the Three-Year Re-inspection. The results of the AHERA Three-Year Re-inspection IX are tabulated in the Room by Room log reports located in *Section II-C* of this report.

As previously noted, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Section I – C.1

Post Management Plan Activities/Changes

Information on activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following: *Sampling and Analysis, New Tile Installation, Abatement Activity and Periodic Six-Month Surveillance Data.*

Sampling and Analysis

In the event that Sampling occurs, data will be listed here.

Section I – C.2

Information on the installation of new floor tiles/renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

New Floor Tile Sampling

In the event that new tile is installed, the material must be tested prior to installation.

Section I – C.3

Information on the Asbestos Abatement and renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

Abatement Activity

In the event Abatement occurs, data will be listed here.

Section I – C.4

Information on the AHERA inspection that noted damage to various Building Materials at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Work orders are created for Corrective Action responses and tracked for completion. Updates to the Management Plan include the following:

Periodic (Six-Month) Surveillance (Damaged Materials)

<i>Date</i>	<i>Element</i>	<i>Floor</i>	<i>On Site Room Name</i>	<i>Material</i>	<i>Amount of Material</i>	<i>Amount of Damage</i>
08/04/2016	1	B	Boy's Showers in Former Boy's Restroom	Pipe Fitting Insulation	11 EA	2 EA
08/04/2016	1	B	Blower Room	Vibration Damper Cloth	1 SF	1 SF
08/04/2016	1	1	Classroom 101	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Classroom 101	Linoleum Sills	50 SF	50 SF
08/04/2016	1	1	Classroom 102	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Classroom 102	Linoleum Sills	50 SF	50 SF
08/04/2016	1	1	Classroom 103	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Classroom 103	Linoleum Sills	50 SF	50 SF
08/04/2016	1	1	Classroom 104	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Classroom 104	Linoleum Sills	50 SF	50 SF
08/04/2016	1	1	Classroom 105	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Classroom 105	Linoleum Sills	50 SF	50 SF
08/04/2016	1	1	Classroom 106	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Classroom 106	Linoleum Sills	50 SF	50 SF
08/04/2016	1	1	Main Office	Window Glaze	140 SF	140 SF
08/04/2016	1	1	Main Office	Linoleum Sills	10 SF	10 SF
08/04/2016	1	2	Classroom 201	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Classroom 201	Linoleum Sills	50 SF	50 SF
08/04/2016	1	2	Classroom 202	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Classroom 202	Linoleum Sills	50 SF	50 SF
08/04/2016	1	2	Classroom 203	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Classroom 203	Linoleum Sills	50 SF	50 SF
08/04/2016	1	2	Classroom 204	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Classroom 204	Linoleum Sills	50 SF	50 SF
08/04/2016	1	2	Classroom 205	Window Glaze	140 SF	140 SF

<i>Date</i>	<i>Element</i>	<i>Floor</i>	<i>On Site Room Name</i>	<i>Material</i>	<i>Amount of Material</i>	<i>Amount of Damage</i>
08/04/2016	1	2	Classroom 205	Linoleum Sills	50 SF	50 SF
08/04/2016	1	2	Classroom 206	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Classroom 206	Linoleum Sills	50 SF	50 SF
08/04/2016	1	2	Computer Network Room in the Teacher's Lounge	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Computer Network Room in the Teacher's Lounge	Linoleum Sills	20 SF	20 SF
08/04/2016	1	2	Boy's Restroom	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Boy's Restroom	Linoleum Sills	5 SF	5 SF
08/04/2016	1	2	Girl's Restroom	Window Glaze	140 SF	140 SF
08/04/2016	1	2	Girl's Restroom	Linoleum Sills	5 SF	5 SF
08/04/2016	1	3	Hallway	Pipe Fitting Insulation	2 EA	2 EA
08/04/2016	1	3	Classroom 301	Window Glaze	140 SF	140 SF
08/04/2016	1	3	Classroom 301	Linoleum Sills	50 SF	50 SF
08/04/2016	1	3	Classroom 302	Window Glaze	140 SF	140 SF
08/04/2016	1	3	Classroom 302	Linoleum Sills	50 SF	50 SF
08/04/2016	1	3	Classroom 303	Window Glaze	140 SF	140 SF
08/04/2016	1	3	Classroom 303	Linoleum Sills	50 SF	50 SF
08/04/2016	1	3	Classroom 304	Window Glaze	140 SF	140 SF
08/04/2016	1	3	Classroom 304	Linoleum Sills	50 SF	50 SF
08/04/2016	1	3	Classroom 305	Plaster Walls	800 SF	800 SF
08/04/2016	1	3	Classroom 305	Window Glaze	140 SF	140 SF
08/04/2016	1	3	Classroom 305	Linoleum Sills	50 SF	50 SF
08/04/2016	1	3	Classroom 306	Window Glaze	140 SF	140 SF
08/04/2016	1	3	Classroom 306	Linoleum Sills	50 SF	50 SF
08/04/2016	1	3	Office between North Stairs and Classroom 306	Window Glaze	100 SF	100 SF
08/04/2016	1	3	Office between North Stairs and Classroom 306	Linoleum Sills	10 SF	10 SF
08/04/2016	1	3	Office between North Stairs and Classroom 306 Restroom	Plaster Walls	100SF	100SF
08/04/2016	1	3	Boy's Restroom	Window Glaze	100 SF	100 SF
08/04/2016	1	3	Boy's Restroom	Linoleum Sills	10 SF	10 SF

Section II Re-inspection Data

- A. Introduction
- B. Re-inspection Key Definitions
- C. Room by Room Asbestos Location Log

Section II - A

Re-inspection Data

Introduction

The following information documents the Three-Year Re-inspection IX of the subject school/facility. The Homogeneous Area Reports were produced using the building inspector's field data on the facility. The key to the Homogeneous Area Report is outlined in the following pages of this report.

Section II - B
(page 1 of 4)

SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE YEAR RE-INSPECTION IX

ITEM	DEFINITION
ULCS#	Individual identification number assigned to each school within the School District of Philadelphia.
HOMOGENEOUS AREA ID#	Identification number assigned to each homogeneous area in a school/facility. Each section of the homogeneous area ID is significant. 1010/01/01/01 A B C D A. Is the ULCS# for the school. B. Designates the specific building/building area within the school. C. Designates the floor or level within the building/building area. D. Designates the homogeneous material within that floor or level. Note: Item D may be a number or a letter.
SYSTEM AFFECTED	Corresponds to the AHERA system for classifying materials. T : Thermal System S : Surfacing System M : Miscellaneous
ITEM AFFECTED	Is a description of the homogeneous material.
ORIGINAL INSPECTION DATA	This section contains the information found in the original Management Plan (1988-1989).
AMOUNT OF MATERIAL/ UNIT	Quantity of material, and measuring unit. Units include: Square Feet (SF) Each (EA) Linear Feet (LF) Cubic Feet (CF).

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

ITEM	DEFINITION
CND Condition	Corresponds to AHERA condition rating for materials. 0 : No Damage 1 : Damage 2 : Significant Damage
DP Damage Potential	Corresponds to the AHERA material assessment system. 1 : Potential for Damage 2 : Potential for Significant Damage
ASMD Assumed Asbestos	This means that a material was not sampled for asbestos content during the original Management Plan inspection.
RA Response Action	This corresponds to the AHERA system of response action rating for materials. 1 : Establish O&M Program 2 : Repair and Establish O&M Program 3 : Enclose 4 : Encapsulate 5 : Remove 6 : Partial Removal and Establish O&M Program
CHANGES	This section describes changes to the homogeneous material in the twenty-four years since the original AHERA inspection. The abbreviations are defined below. RMVD : Removed ENCL : Enclosed ENCP : Encapsulated DMGD : Damaged SMPLD : Sampled MTRL : Material RPRD : Repaired N/L : None Located RPLCD : Replaced

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE-YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

ITEM	DEFINITION
THREE YEAR RE-INSPECTION	This section contains the information obtained from the Three-Year Re-inspection IX. With three exceptions, the information categories are identical in format and meaning to those found in the original inspection data section. The three exceptions are defined below.
DMGD AMT Amount Damaged	This section gives the quantity of damaged material in a homogeneous area. The quantity is shown in the same format as the amount of material/unit section.
NF Newly Friable	This section identifies materials in the original Management Plan which have since become friable.
RA Response Action	<p>This rating is based on the AHERA regulations, and is comparable to the RA rating found in the "Original Inspection Data" section. The following table details the response actions.</p> <ol style="list-style-type: none">1. Establish O&M Program2. Repair and Establish O&M Program3. Enclose4. Encapsulate5. Remove6. Partial Removal and Establish O&M Program <ol style="list-style-type: none">a. High Priority Response The homogeneous material has been scheduled for abatement or other response action.b. Medium Priority Response The homogeneous material will be scheduled for abatement or other response action as soon as the high priority responses have been addressed.c. Low Priority Response The homogeneous material will be scheduled for abatement or other response action as soon as the medium priority responses have been addressed.d. On-Going Response/Operations and Maintenance The homogeneous material does not require abatement or other response action at present, and should be included in the facility's on-going operations and maintenance program.

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE-YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

The information presented in the changes section has been compiled from a variety of sources, including the Re-inspection and the following:

- * Quality Control/Quality Assurance Reports of asbestos abatement projects, prepared by consultants to the School District.
- * Permit and Notification Forms for asbestos abatement projects.
- * Periodic Surveillance Forms
- * Operations and Maintenance activities performed by School District personnel.
- * Verbal information from School District personnel.
- * Reports of sampling and analysis of suspected materials by both School District personnel and outside consultants.

**ROOM BY
ROOM
LOCATION LOG
REPORT**

This section gives information, including damage amount and location, for a specific homogeneous material on a room-by-room basis and follows the Re-inspection form.

NOTE: The disparate nature of the above sources of information prohibits the verification of much information within the scope of the AHERA Three-Year Re-inspection . Discrepancies and omissions may exist in this information, and therefore is included on an "as is" basis. The inspectors for the Three-Year Re-inspection IX evaluated homogeneous areas based on the materials current condition and location, as evidenced during the inspector's site visit.

Section II - C

Room by Room Location Log Report

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location.

NOTE:

Contact OEMS prior to the disturbance of any of the materials that are listed as Confirmed and/or Assumed.

The quantities listed for (NAD) non-asbestos containing materials and/or Non-Suspect Materials are only estimated and were not measured for the purpose of this report. Field verification of quantities for renovation purposes would be necessary.

5330/5690 El Centro de Estudiantes School/Big Picture Philadelphia HS 2015-2016 AHERA Three-Year Report.xls

School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 1/14/16						
Big Picture Philadelphia High School (El Centro de Estudiantes)		Room by Room Location Log Report										Building Inspector: Alex Roman						
136 Dauphin Street Philadelphia, PA 19133												Certificate Number: EHSBIR-150619-008						
ULCS# 5330												Management Planner: Monique Causley						
Year Built: 1935												Certificate Number: ACC-0215-8-010						
Element	Room	System Affected	Material Description	HID#	Confirmed Non Suspect ACM	Assumed NAD	Amount of Material	SF EA	LF EA	Amount of Damage	SF EA	LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawlspace Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	B	Main Mechanical Room at the bottom of the North Stairs	N/A	Brick Wall		Non Suspect ACM	2000	SF	0							N/A	N/A	N/A
1	B	Main Mechanical Room at the bottom of the North Stairs	N/A	Brick Floor		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Main Mechanical Room at the bottom of the North Stairs	N/A	Concrete Ceiling		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Main Mechanical Room at the bottom of the North Stairs	N/A	Boiler Breeching		NAD	300	LF	0							N/A	N/A	N/A
1	B	Main Mechanical Room at the bottom of the North Stairs	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	1000	SF	0							N/A	N/A	N/A
1	B	Pump Room attached to Main Mechanical Room to the South	N/A	Concrete Block Wall		Non Suspect ACM	1000	SF	0							N/A	N/A	N/A
1	B	Pump Room attached to Main Mechanical Room to the South	N/A	Concrete Ceiling		Non Suspect ACM	1000	SF	0							N/A	N/A	N/A
1	B	Pump Room attached to Main Mechanical Room to the South	N/A	Cement Floor		Non Suspect ACM	1000	SF	0							N/A	N/A	N/A
1	B	Pump Room attached to Main Mechanical Room to the South	N/A	Brick Wall		Non Suspect ACM	1000	SF	0							N/A	N/A	N/A
1	B	Pump Room attached to Main Mechanical Room to the South	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	100	LF	0							N/A	N/A	N/A
1	B	Former Boy's Restroom	N/A	Cement Floor		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Former Boy's Restroom	N/A	Concrete Ceiling		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Former Boy's Restroom	N/A	Brick Wall		Non Suspect ACM	2000	SF	0							N/A	N/A	N/A
1	B	Former Boy's Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	300	LF	0							N/A	N/A	N/A
1	B	Former Boy's Restroom	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	50	EA	0							1	No	1/D
1	B	Former Boy's Restroom	M	Transite Stalls	5330/01/0B/04	Assumed	500	SF	0							1	No	1/D
1	B	Former Boy's Restroom	M	Transite Urinal Covers	5330/01/0B/04	Assumed	200	SF	0							1	No	1/D
1	B	Boy's Showers in Former Boy's Restroom	M	Sheetrock Wall	5330/01/0B/VER/AR/2100	Assumed	500	SF	0							1	No	1/D
1	B	Boy's Showers in Former Boy's Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0							N/A	N/A	N/A
1	B	Boy's Showers in Former Boy's Restroom	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	11	EA	2	EA						1	Yes	2/A
1	B	Boy's Showers in Former Boy's Restroom	N/A	Ceramic Tile Walls		Non Suspect ACM	400	SF	0							N/A	N/A	N/A
1	B	Boy's Showers in Former Boy's Restroom	N/A	Cement Floor		Non Suspect ACM	300	SF	0							N/A	N/A	N/A
1	B	Empty Space blocked off behind the stalls in the Boy's Restroom	x	x	x	x	x	x	x	x	x	x	x	No Acces, No Doors, blocked off with 500sf Sheet Rock		x	x	x
1	B	South Stairs	N/A	Cement Floor		Non Suspect ACM	250	SF	0							N/A	N/A	N/A
1	B	South Stairs	N/A	Concrete Ceiling		Non Suspect ACM	250	SF	0							N/A	N/A	N/A
1	B	South Stairs	N/A	Plaster Walls		NAD	400	SF	0							N/A	N/A	N/A
1	B	North Stairs	N/A	Cement Floor		Non Suspect ACM	250	SF	0							N/A	N/A	N/A
1	B	North Stairs	N/A	Concrete Ceiling		Non Suspect ACM	250	SF	0							N/A	N/A	N/A
1	B	North Stairs	N/A	Plaster Walls		NAD	400	SF	0							N/A	N/A	N/A
1	B	Small Area at the base of the South Stairs used as Cafeteria in front of the Boy's Restroom	N/A	Cement Floor		Non Suspect ACM	400	SF	0							N/A	N/A	N/A
1	B	Small Area at the base of the South Stairs used as Cafeteria in front of the Boy's Restroom	N/A	Brick Wall		Non Suspect ACM	700	SF	0							N/A	N/A	N/A
1	B	Small Area at the base of the South Stairs used as Cafeteria in front of the Boy's Restroom	N/A	Concrete Ceiling		Non Suspect ACM	400	SF	0							N/A	N/A	N/A
1	B	Small Area at the base of the South Stairs used as Cafeteria in front of the Boy's Restroom	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	19	EA	0							1	No	1/D
1	B	Small Area at the base of the South Stairs used as Cafeteria in front of the Boy's Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	70	LF	0							N/A	N/A	N/A
1	B	Cafeteria	N/A	Brick Wall		Non Suspect ACM	2000	SF	0							N/A	N/A	N/A
1	B	Cafeteria	N/A	Cement Floor		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Cafeteria	N/A	Concrete Ceiling		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Cafeteria	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	4	EA	0							1	No	1/D
1	B	Cafeteria	T	Pipe Insulation 2-6 inch	5330/01/0B/01	Confirmed	40	LF	0							1	No	1/D
1	B	Cafeteria	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	35	LF	0							N/A	N/A	N/A
1	B	Hallway from the Cafeteria to the Girl's Restrom	N/A	Cement Floor		Non Suspect ACM	1200	SF	0							N/A	N/A	N/A
1	B	Hallway from the Cafeteria to the Girl's Restrom	N/A	Concrete Ceiling		Non Suspect ACM	1200	SF	0							N/A	N/A	N/A
1	B	Hallway from the Cafeteria to the Girl's Restrom	N/A	Brick Wall		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Hallway from the Cafeteria to the Girl's Restrom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	250	LF	0							N/A	N/A	N/A
1	B	Hallway from the Cafeteria to the Girl's Restrom	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	82	EA	0							1	No	1/D
1	B	Former Girl's Restroom	N/A	Cement Floor		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Former Girl's Restroom	N/A	Brick Wall		Non Suspect ACM	2000	SF	0							N/A	N/A	N/A
1	B	Former Girl's Restroom	N/A	Concrete Ceiling		Non Suspect ACM	1500	SF	0							N/A	N/A	N/A
1	B	Former Girl's Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	100	LF	0							N/A	N/A	N/A
1	B	Former Girl's Restroom	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	36	EA	0							1	No	1/D
1	B	Former Girl's Restroom	T	Pipe Insulation 2-6 inch	5330/01/0B/01	Confirmed	100	LF	0							1	No	1/D
1	B	Former Girl's Restroom	M	Transite Stalls	5330/01/0B/04	Assumed	28	SF	0							1	No	1/D
1	B	Former Girl's Restroom	M	Sheetrock Wall	5330/01/0B/VER/AR/2100	Assumed	300	SF	0							1	No	1/D
1	B	Former Girl's Showers in Girl's Restroom	N/A	Ceramic Tile Walls		Non Suspect ACM	300	SF	0							N/A	N/A	N/A
1	B	Former Girl's Showers in Girl's Restroom	N/A	Cement Floor		Non Suspect ACM	300	SF	0							N/A	N/A	N/A
1	B	Former Girl's Showers in Girl's Restroom	N/A	Concrete Ceiling		Non Suspect ACM	300	SF	0							N/A	N/A	N/A
1	B	Former Girl's Showers in Girl's Restroom	N/A	Brick Wall		Non Suspect ACM	500	SF	0							N/A	N/A	N/A
1	B	Former Girl's Showers in Girl's Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0							N/A	N/A	N/A
1	B	Former Girl's Showers in Girl's Restroom	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	3	EA	0							1	No	1/D
1	B	Closet at the South wall by the Fire Stairs	N/A	Cement Floor		Non Suspect ACM	100	SF	0							N/A	N/A	N/A
1	B	Closet at the South wall by the Fire Stairs	N/A	Concrete Ceiling		Non Suspect ACM	100	SF	0							N/A	N/A	N/A
1	B	Closet at the South wall by the Fire Stairs	N/A	Brick Wall		Non Suspect ACM	100	SF	0							N/A	N/A	N/A
1	B	Closet at the South wall by the Fire Stairs	N/A	Concrete Block Wall		Non Suspect ACM	100	SF	0							N/A	N/A	N/A
1	B	Fire Stairs	N/A	Ceramic Tile Walls		Non Suspect ACM	200	SF	0							N/A	N/A	N/A

5330/5690 El Centro de Estudiantes School/Big Picture Philadelphia HS 2015-2016 AHERA Three-Year Report.xls

		School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016							Reinspection Date: 1/14/16					
		Big Picture Philadelphia High School (El Centro de Estudiantes)		Room by Room Location Log Report							Building Inspector: Alex Roman					
		136 Dauphin Street Philadelphia, PA 19133									Certificate Number: EHSBIR-150619-008					
		ULCS# 5330									Management Planner: Monique Causley					
		Year Built: 1935									Certificate Number: ACC-0215-8-010					
Element	Room	On Site Room Name	System Affected	Material Description	HID#	Confirmed Assumed NAD Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawlspace Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	B	Fire Stairs	N/A	Concrete Ceiling		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Fire Stairs	N/A	Cement Floor		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Blower Room	N/A	Cement Floor		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	B	Blower Room	N/A	Concrete Ceiling		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	B	Blower Room	N/A	Brick Wall		Non Suspect ACM	700	SF	0				N/A	N/A	N/A	
1	B	Blower Room	M	Vibration Dampener Cloth	5330/01/0B/05	Assumed	1	EA	1		EA		1	No	5/C	
1	B	Storage Closet next to the entrance to the Blower Room	N/A	Cement Floor		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Storage Closet next to the entrance to the Blower Room	N/A	Concrete Ceiling		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Storage Closet next to the entrance to the Blower Room	N/A	Brick Wall		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Hallway in front of the closet and Blower Room Entrance	N/A	Cement Floor		Non Suspect ACM	1000	SF	0				N/A	N/A	N/A	
1	B	Hallway in front of the closet and Blower Room Entrance	N/A	Brick Wall		Non Suspect ACM	1000	SF	0				N/A	N/A	N/A	
1	B	Hallway in front of the closet and Blower Room Entrance	N/A	Concrete Ceiling		Non Suspect ACM	1000	SF	0				N/A	N/A	N/A	
1	B	Hallway in front of the closet and Blower Room Entrance	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	45	LF	0				N/A	N/A	N/A	
1	B	Hallway in front of the closet and Blower Room Entrance	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	3	EA	0				1	No	1/D	
1	B	Hallway in front of the closet and Blower Room Entrance	T	Pipe Insulation > 6 inch	5330/01/0B/02	Confirmed	35	LF	0				1	No	1/D	
1	B	Mechanical Room that connects to the Blower Room Labeled C3	N/A	Cement Floor		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	B	Mechanical Room that connects to the Blower Room Labeled C3	N/A	Concrete Ceiling		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	B	Mechanical Room that connects to the Blower Room Labeled C3	N/A	Brick Wall		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	B	Mechanical Room that connects to the Blower Room Labeled C3	T	Pipe Insulation 2-6 inch	5330/01/0B/01	Confirmed	10	LF	0				1	No	1/D	
1	B	Mechanical Room that connects to the Blower Room Labeled C3	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	2	EA	0				1	No	1/D	
1	B	Mechanical Room that connects to the Blower Room Labeled C3	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0				N/A	N/A	N/A	
1	B	Area behind Kitchen (Walled Off)	x	x	x	x	x	x	x				x	x	x	
1	B	Hallway leading to the Water Pump Room	M	Floor Tile VAT 12" x 12"	5330/01/0B/KK	Assumed	200	SF	0			Tan	1	No	1/D	
1	B	Hallway leading to the Water Pump Room	N/A	Concrete Ceiling		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Hallway leading to the Water Pump Room	N/A	Brick Wall		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Water Pump Room gated off	N/A	Cement Floor		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Water Pump Room gated off	N/A	Brick Wall		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Water Pump Room gated off	N/A	Concrete Ceiling		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	B	Water Pump Room gated off	T	Pipe Fitting Insulation	5330/01/0B/07	Confirmed	8	EA	0				1	No	1/D	
1	B	Water Pump Room gated off	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0				N/A	N/A	N/A	
1	B	Kitchen	M	Floor Tile VAT 12" x 12"	5330/01/0B/KK	Assumed	800	SF	0				1	No	1/D	
1	B	Kitchen	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	B	Kitchen	N/A	Brick Wall		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	B	Kitchen	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0				N/A	N/A	N/A	
1	1	Classroom 101	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 101	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 101	N/A	Plaster Walls		NAD	1200	SF	0				N/A	N/A	N/A	
1	1	Classroom 101	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140		LF	Grey	1	No	5/C	
1	1	Classroom 101	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50		SF		1	No	5/C	
1	1	Classroom 101	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	1	Classroom 102	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 102	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 102	N/A	Plaster Walls		NAD	1200	SF	0				N/A	N/A	N/A	
1	1	Classroom 102	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140		LF	Grey	1	No	5/C	
1	1	Classroom 102	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50		SF		1	No	5/C	
1	1	Classroom 103	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 103	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 103	N/A	Plaster Walls		NAD	1200	SF	0				N/A	N/A	N/A	
1	1	Classroom 103	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140		LF	Grey	1	No	5/C	
1	1	Classroom 103	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50		SF		1	No	5/C	
1	1	Classroom 103	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	1	Classroom 103	M	Floor Tile VAT 9" x 9"	5330/01/01/10	Confirmed	200	SF	0			Tan	1	No	1/D	
1	1	Classroom 104	M	Floor Tile VAT 12" x 12"	5330/01/01/11	Assumed	800	SF	0			Tan	1	No	1/D	
1	1	Classroom 104	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 104	N/A	Plaster Walls		NAD	1200	SF	0				N/A	N/A	N/A	
1	1	Classroom 104	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140		LF	Grey	1	No	5/C	
1	1	Classroom 104	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50		SF		1	No	5/C	
1	1	Classroom 104	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	1	Classroom 104	N/A	Wall Paper		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 105	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 105	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 105	N/A	Plaster Walls		NAD	1200	SF	0				N/A	N/A	N/A	
1	1	Classroom 105	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140		LF	Grey	1	No	5/C	
1	1	Classroom 105	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50		SF		1	No	5/C	
1	1	Classroom 106	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 106	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Classroom 106	N/A	Plaster Walls		NAD	1200	SF	0				N/A	N/A	N/A	
1	1	Classroom 106	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140		LF	Grey	1	No	5/C	

5330/5690 El Centro de Estudiantes School/Big Picture Philadelphia HS 2015-2016 AHERA Three-Year Report.xls

E l e m e n t	F l o o r	School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016											Reinspection Date: 1/14/16	
		Big Picture Philadelphia High School (El Centro de Estudiantes)		Room by Room Location Log Report											Building Inspector: Alex Roman	
		136 Dauphin Street Philadelphia, PA 19133													Certificate Number: EHSBR-150619-008	
		ULCS# 5330													Management Planner: Monique Causley	
Year Built: 1935													Certificate Number: ACC-0215-8-010			
On Site Room Name		System Affected	Material Description	HID#	Confirmed Assumed NAD Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawlspace Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)	
1	1	Classroom 106	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	1	Classroom 106	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	1	Main Office	M	Floor Tile VAT 12" x 12"	5330/01/01/JJ	Assumed	500	SF	0				1	No	1/D	
1	1	Main Office	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	1	Main Office	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	1	Main Office	M	Window Glaze	5330/01/01/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	1	Main Office	M	Linoleum Sills	5330/01/01/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	1	Principal's Office across from Main Office	M	Floor Tile VAT 12" x 12"	5330/01/01/JJ	Assumed	400	SF	0				1	No	1/D	
1	1	Principal's Office across from Main Office	N/A	Plaster Walls		NAD	400	SF	0				N/A	N/A	N/A	
1	1	Principal's Office across from Main Office	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	400	SF	0				N/A	N/A	N/A	
1	1	Office across from Men's Restroom	x	x	x	x	x	x	x	x	x		x	x	x	
1	1	Girl's Restroom	x	x	x	x	x	x	x	x	x		x	x	x	
1	1	Boy's Restroom	M	Linoleum	5330/01/01/VER/AR/2200	Assumed	300	SF	0				1	No	1/D	
1	1	Boy's Restroom	N/A	Plaster Walls		NAD	300	SF	0				N/A	N/A	N/A	
1	1	Boy's Restroom	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	300	SF	0				N/A	N/A	N/A	
1	1	Fire Tower	N/A	Cement Floor		Non Suspect ACM	300	SF	0				N/A	N/A	N/A	
1	1	Fire Tower	N/A	Brick Wall		Non Suspect ACM	300	SF	0				N/A	N/A	N/A	
1	1	Fire Tower	N/A	Ceramic Tile Walls		Non Suspect ACM	300	SF	0				N/A	N/A	N/A	
1	1	Fire Tower	N/A	Concrete Ceiling		Non Suspect ACM	300	SF	0				N/A	N/A	N/A	
1	1	Hallway on First Floor	N/A	Cement Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Hallway on First Floor	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	1	Hallway on First Floor	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	1	Hallway on First Floor	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	55	LF	0				N/A	N/A	N/A	
1	1	North Stairwell	N/A	Cement Floor		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	1	North Stairwell	N/A	Concrete Ceiling		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	1	North Stairwell	N/A	Concrete Block Wall		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	1	South Stairwell	N/A	Cement Floor		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	1	South Stairwell	N/A	Concrete Ceiling		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	1	South Stairwell	N/A	Concrete Block Wall		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	
1	2	Classroom 201	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 201	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 201	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 201	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	2	Classroom 201	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	2	Classroom 201	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Classroom 202	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 202	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 202	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 202	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	2	Classroom 202	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	2	Classroom 202	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Classroom 203	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 203	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 203	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 203	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	2	Classroom 203	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	2	Classroom 204	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 204	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 204	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 204	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	2	Classroom 204	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	2	Classroom 204	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Classroom 205	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 205	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 205	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 205	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	2	Classroom 205	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	2	Classroom 205	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Classroom 206	N/A	Wood Floor		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 206	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 206	N/A	Plaster Walls		NAD	800	SF	0				N/A	N/A	N/A	
1	2	Classroom 206	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed	140	LF	140	LF	Grey		1	No	5/C	
1	2	Classroom 206	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed	50	SF	50	SF			1	No	5/C	
1	2	Classroom 206	N/A	Partition Room Dividers		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Teacher's Lounge outside Classroom 206	N/A	Wood Floor		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Teacher's Lounge outside Classroom 206	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM	500	SF	0				N/A	N/A	N/A	
1	2	Teacher's Lounge outside Classroom 206	N/A	Plaster Walls		NAD	500	SF	0				N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge	N/A	Wood Floor		Non Suspect ACM	200	SF	0				N/A	N/A	N/A	

5330/5690 El Centro de Estudiantes School/Big Picture Philadelphia HS 2015-2016 AHERA Three-Year Report.xls

Element		School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 1/14/16							
		Big Picture Philadelphia High School (El Centro de Estudiantes)		Room by Room Location Log Report										Building Inspector: Alex Roman							
		136 Dauphin Street Philadelphia, PA 19133												Certificate Number: EHSBIR-150619-008							
		ULCS# 5330												Management Planner: Monique Causley							
		Year Built: 1935												Certificate Number: ACC-0215-8-010							
		On Site Room Name	System Affected	Material Description	HID#	Confirmed Non Suspect ACM	Assumed NAD	Amount of Material	SF	LF	EA	Amount of Damage	SF	LF	EA	Color required for VAT	Comments/Description/Notes	Attic/Crawlspace Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	2	Computer Network Room in the Teacher's Lounge	N/A	Plaster Walls		NAD		300	SF		0							N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge	M	Sheetrock Wall	5330/01/02/VER/AR/2100	Assumed		200	SF		0							1	No	1/D	
1	2	Computer Network Room in the Teacher's Lounge	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed		140	LF		140		LF		Grey			1	No	5/C	
1	2	Computer Network Room in the Teacher's Lounge	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed		20	SF		20		SF					N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge Closet	N/A	Wood Floor		Non Suspect ACM		100	SF		0							N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge Closet	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		100	SF		0							N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge Closet	N/A	Plaster Walls		NAD		100	SF		0							N/A	N/A	N/A	
1	2	Computer Network Room in the Teacher's Lounge Closet	N/A	Fiberglass Pipe Insulation		Non Suspect ACM		20	LF		0							N/A	N/A	N/A	
1	2	Hallway on the Second Floor	N/A	Cement Floor		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	2	Hallway on the Second Floor	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	2	Hallway on the Second Floor	N/A	Plaster Walls		NAD		800	SF		0							N/A	N/A	N/A	
1	2	Hallway on the Second Floor	N/A	Fiberglass Pipe Insulation		Non Suspect ACM		55	LF		0							N/A	N/A	N/A	
1	2	Office across from Teacher's Lounge	N/A	Wall Paper		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	
1	2	Office across from Teacher's Lounge	N/A	Plaster Walls		NAD		500	SF		0							N/A	N/A	N/A	
1	2	Office across from Teacher's Lounge	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	
1	2	Office across from Teacher's Lounge	N/A	Wood Floor		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	
1	2	Teen Parent Room across from Restrooms	N/A	Wall Paper		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	
1	2	Teen Parent Room across from Restrooms	S	Plaster Ceiling	5330/01/02/VER/AR/1900	Assumed		500	SF		0							1	No	1/D	
1	2	Teen Parent Room across from Restrooms	N/A	Plaster Walls		NAD		500	SF		0							N/A	N/A	N/A	
1	2	Teen Parent Room across from Restrooms	N/A	Wood Floor		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	
1	2	Boy's Restroom	N/A	Wall Paper		Non Suspect ACM		300	SF		0							N/A	N/A	N/A	
1	2	Boy's Restroom	M	Floor Tile VAT 12" x 12"	5330/01/02/A5	Assumed		300	SF		0				Brown			1	No	1/D	
1	2	Boy's Restroom	M	Transite Stalls	5330/01/02/VER/AR/2609	Assumed		14	SF		0							1	No	1/D	
1	2	Boy's Restroom	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		300	SF		0							N/A	N/A	N/A	
1	2	Boy's Restroom	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed		140	LF		140		LF		Grey			1	No	5/C	
1	2	Boy's Restroom	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed		5	SF		5		SF					1	No	5/C	
1	2	Boy's Restroom	N/A	Plaster Walls		NAD		300	SF		0							N/A	N/A	N/A	
1	2	Girl's Restroom	M	Transite Stall	5330/01/02/UJ	Assumed		x	x		x		x		x	Need square footage of material		x	x	x	
1	2	Girl's Restroom	M	Transite Walls	5330/01/02/UJ	Assumed		x	x		x		x		x	Need square footage of material		x	x	x	
1	2	Girl's Restroom	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		300	SF		0							N/A	N/A	N/A	
1	2	Girl's Restroom	M	Window Glaze	5330/01/02/VER/AR/2609	Assumed		140	LF		140		LF		Grey			1	No	5/C	
1	2	Girl's Restroom	M	Linoleum Sills	5330/01/02/VER/AP/2201	Assumed		5	SF		5		SF					1	No	5/C	
1	2	Girl's Restroom	M	Sheetrock Wall	5330/01/02/VER/AR/2100	Assumed		200	SF		0							1	No	1/D	
1	2	Fire Tower	N/A	Ceramic Tile Walls		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	Fire Tower	N/A	Cement Floor		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	Fire Tower	N/A	Concrete Ceiling		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	North Stairs	N/A	Cement Floor		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	North Stairs	N/A	Concrete Ceiling		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	North Stairs	N/A	Concrete Block Wall		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	South Stairs	N/A	Cement Floor		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	South Stairs	N/A	Concrete Ceiling		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	2	South Stairs	N/A	Concrete Block Wall		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	North Stairs	N/A	Cement Floor		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	North Stairs	N/A	Concrete Ceiling		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	North Stairs	N/A	Concrete Block Wall		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	South Stairs	N/A	Cement Floor		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	South Stairs	N/A	Concrete Ceiling		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	South Stairs	N/A	Concrete Block Wall		Non Suspect ACM		200	SF		0							N/A	N/A	N/A	
1	3	Hallway	N/A	Cement Floor		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	3	Hallway	N/A	Plaster Walls		NAD		800	SF		0							N/A	N/A	N/A	
1	3	Hallway	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF		0						Plaster Ceiling above 2 X 4 Tiles were CONFIRMED in Rooms 306, 310 and Third Floor Hallway. Sampled 1992	N/A	N/A	N/A	
1	3	Hallway	S	Plaster Ceiling	5330/01/03/DD	Confirmed		800	SF		0							1	No	1/D	
1	3	Hallway	T	Pipe Fitting Insulation	5330/01/03/VER/AR/1120	Assumed		2	EA		2		EA					1	Yes	2/A	
1	3	Classroom 301	N/A	Wood Floor		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	3	Classroom 301	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	3	Classroom 301	N/A	Plaster Walls		NAD		800	SF		0							N/A	N/A	N/A	
1	3	Classroom 301	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		140	LF		140		LF		Grey			1	No	5/C	
1	3	Classroom 301	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		50	SF		50		SF					1	No	5/C	
1	3	Classroom 301	N/A	Partition Room Dividers		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	
1	3	Classroom 302	N/A	Wood Floor		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	3	Classroom 302	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF		0							N/A	N/A	N/A	
1	3	Classroom 302	N/A	Plaster Walls		NAD		800	SF		0							N/A	N/A	N/A	
1	3	Classroom 302	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		140	LF		140		LF		Grey			1	No	5/C	
1	3	Classroom 302	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		50	SF		50		SF					1	No	5/C	
1	3	Classroom 302	N/A	Partition Room Dividers		Non Suspect ACM		500	SF		0							N/A	N/A	N/A	

5330/5690 El Centro de Estudiantes School/Big Picture Philadelphia HS 2015-2016 AHERA Three-Year Report.xls

		School District of Philadelphia Big Picture Philadelphia High School (El Centro de Estudiantes) 136 Dauphin Street Philadelphia, PA 19133 ULCS# 5330 Year Built: 1935		AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report							Reinspection Date: 1/14/16 Building Inspector: Alex Roman Certificate Number: EHSBIR-150619-008 Management Planner: Monique Causley Certificate Number: ACC-0215-8-010						
Element	Room	On Site Room Name	System Affected	Material Description	HID#	Confirmed Non Suspect ACM	Assumed NAD	Amount of Material	SF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawlspace Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	3	Classroom 303	N/A	Wood Floor		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 303	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 303	N/A	Plaster Walls		NAD		800	SF	0					N/A	N/A	N/A
1	3	Classroom 303	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		140	LF	140	LF	Grey			1	No	5/C
1	3	Classroom 303	N/A	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		50	SF	50	SF				1	No	5/C
1	3	Classroom 303	N/A	Partition Room Dividers		Non Suspect ACM		500	SF	0					N/A	N/A	N/A
1	3	Classroom 304	N/A	Wood Floor		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 304	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 304	N/A	Plaster Walls		NAD		800	SF	0					N/A	N/A	N/A
1	3	Classroom 304	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		140	LF	140	LF	Grey			1	No	5/C
1	3	Classroom 304	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		50	SF	50	SF				1	No	5/C
1	3	Classroom 304	N/A	Partition Room Dividers		Non Suspect ACM		500	SF	0					N/A	N/A	N/A
1	3	Classroom 305	N/A	Wood Floor		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 305	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 305	N/A	Plaster Walls		NAD		800	SF	3	SF				N/A	N/A	N/A
1	3	Classroom 305	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		140	LF	140	LF	Grey			1	No	5/C
1	3	Classroom 305	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		50	SF	50	SF				1	No	5/C
1	3	Classroom 305	N/A	Partition Room Dividers		Non Suspect ACM		500	SF	0					N/A	N/A	N/A
1	3	Classroom 306	N/A	Wood Floor		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 306	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		800	SF	0					N/A	N/A	N/A
1	3	Classroom 306	N/A	Plaster Walls		NAD		800	SF	0					N/A	N/A	N/A
1	3	Classroom 306	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		140	LF	140	LF	Grey			1	No	5/C
1	3	Classroom 306	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		50	SF	50	SF				1	No	5/C
1	3	Classroom 306	N/A	Partition Room Dividers		Non Suspect ACM		500	SF	0					N/A	N/A	N/A
1	3	Office between North Stairs and Classroom 306	N/A	Plaster Walls		NAD		500	SF	0					N/A	N/A	N/A
1	3	Office between North Stairs and Classroom 306	N/A	Wood Floor		Non Suspect ACM		500	SF	0					N/A	N/A	N/A
1	3	Office between North Stairs and Classroom 306	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		500	SF	0					N/A	N/A	N/A
1	3	Office between North Stairs and Classroom 306	S	Plaster Ceiling	5330/01/03/DD	Confirmed		500	SF	0			Plaster Ceiling above 2 X 4 Tiles were CONFIRMED in Rooms 306, 310 and Third Floor Hallway. Sampled 1992		1	No	1/D
1	3	Office between North Stairs and Classroom 306	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		100	LF	100	LF	Grey			1	No	5/C
1	3	Office between North Stairs and Classroom 306	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		10	SF	10	SF				1	No	5/C
1	3	Office between North Stairs and Classroom 306 Restroom	N/A	Wood Floor		Non Suspect ACM		100	SF	0					N/A	N/A	N/A
1	3	Office between North Stairs and Classroom 306 Restroom	N/A	Plaster Walls		NAD		100	SF	50	SF				N/A	N/A	N/A
1	3	Office between North Stairs and Classroom 306 Restroom	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		100	SF	0					N/A	N/A	N/A
1	3	Office at the top of the North Stairs next to Classroom 305	N/A	Wood Floor		Non Suspect ACM		400	SF	0					N/A	N/A	N/A
1	3	Office at the top of the North Stairs next to Classroom 305	N/A	Plaster Walls		NAD		400	SF	0					N/A	N/A	N/A
1	3	Office at the top of the North Stairs next to Classroom 305	S	Plaster Ceiling	5330/01/03/DD	Confirmed		400	SF	0			Sampled Positive 1992 in Room 306, 310 and Third Floor Hallway		1	No	1/D
1	3	Office at the top of the South Stairs across from the Restrooms	N/A	Plaster Walls		NAD		300	SF	0					N/A	N/A	N/A
1	3	Office at the top of the South Stairs across from the Restrooms	S	Plaster Ceiling	5330/01/03/DD	Confirmed		300	SF	0					1	No	1/D
1	3	Office at the top of the South Stairs across from the Restrooms	N/A	Wood Floor		Non Suspect ACM		300	SF	0					N/A	N/A	N/A
1	3	Boy's Restroom	M	Floor Tile VAT 12" x 12"	5330/01/03/A6	Assumed		300	SF	0					1	No	1/D
1	3	Boy's Restroom	N/A	Plaster Walls		NAD		300	SF	0					N/A	N/A	N/A
1	3	Boy's Restroom	N/A	Ceiling Tile 2' x 4'		Non Suspect ACM		300	SF	0					N/A	N/A	N/A
1	3	Boy's Restroom	M	Window Glaze	5330/01/03/VER/AR/2609	Assumed		100	LF	100	LF	Grey			1	No	5/C
1	3	Boy's Restroom	M	Linoleum Sills	5330/01/03/VER/AP/2201	Assumed		10	SF	10	SF				1	No	5/C
1	3	Girl's Restroom	M	Floor Tile VAT 9" x 9"	5330/01/03/16	Confirmed		200	SF	0					1	No	1/D
1	3	Girl's Restroom	N/A	Plaster Walls		NAD		200	SF	0					N/A	N/A	N/A
1	3	Girl's Restroom	M	Transite Wall Panels	5330/01/03/CC	Assumed		200	SF	0					1	No	1/D
1	3	Fire Tower	N/A	Cement Floor		Non Suspect ACM		200	SF	0					N/A	N/A	N/A
1	3	Fire Tower	N/A	Ceramic Tile Walls		Non Suspect ACM		200	SF	0					N/A	N/A	N/A
1	3	Fire Tower	N/A	Concrete Ceiling		Non Suspect ACM		200	SF	0					N/A	N/A	N/A
1	A	Attic- Third Floor Stairwell	x	x	x	x	x	x	x	x	x	x	100 LF Air Cell/Elbows/Metal jackets	B	x	x	x
1	C	Crawlspace	x	x	x	x	x	x	x	x	x	x	No Crawlspace	None	x	x	x

Section III Certificates

A. Management Planner/Building Inspector Certificates

Section III – A

Management Planner/Building Inspector Certificates

These charts indicate the Name, Course Date, Expiration Date and Corresponding Certificate Number of the Management Planner and Building Inspector of individuals that participated in the AHERA 3 Year Inspection and Management Plan process of 2015/2016.

Management Planner	Date Granted	Expiration Date	Certificate Number
Monique Causley	2/15/2015	2/16/2016	ACC-0215-8-010
Monique Causley	2/16/2016	2/17/2017	ACC-0216-8-001
Megan Vala	5/22/2015	6/22/2016	740728
Mary Anne Lerro	4/5/2016	4/5/2017	742327

Building Inspector	Date Granted	Expiration Date	Certificate Number
Scott Magee	8/15/2015	8/15/2016	70016699C
William Garrity	8/15/2015	8/15/2016	70016699A
Bernard Brunner	10/2/2015	8/2/2016	45397
Mary Anne Lerro	3/3/2015	3/3/2016	740092
Mary Anne Lerro	4/5/2016	4/5/2017	742322
James Madden	12/11/2014	12/11/2015	ACC-1214-6-010
James Madden	12/3/2015	12/3/2016	ACC-1215-6-018
Troy Ray	3/15/2015	3/19/2016	ACC-0355-6-011
Ananth Vinjamuri	9/29/2015	9/29/2016	374
Shelton Williams	9/29/2015	9/29/2016	375
Paul Davis	2/12/2015	2/12/2016	ACC-0215-6-015
Paul Davis	2/2/2016	2/2/2017	741836
Bernard Bryson	2/16/2015	2/16/2016	ACC-0125-6-031
Bernard Bryson	2/15/2016	2/15/2017	ACC-0216-6-005
Alexander Roman	9/18/2015	9/18/2016	EHSBIR-150619-008
Norm Harrison	9/2/2015	9/2/2016	ACC-0915-6-011
Kelly Mayberry	2/20/2015	2/20/2016	EHSBIR-150220-005
Kelly Mayberry	2/18/2016	2/18/2017	EHSBIR-160218-006
Andrew Hine	5/6/2015	5/6/2016	AI05042015-3
Maryellen Leotta	2/12/2015	2/12/2016	ACC-0215-6-024

Certificate of Completion

awarded to

Monique Causley

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Management Planner Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/16/15

Course Date

N/A

Exam Date

2/16/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-8-010

Certificate Number

Mark K. Schlüger
Training Director



Certificate of Completion

awarded to

Monique Causley

for successfully completing the prescribed course of study in

**Pennsylvania Asbestos Management Planner
Refresher Course**

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/15/16

Course Date

N/A

Exam Date

2/15/17

Expiration Date

Not Provided

Social Security Number

ACC-0216-8-001

Certificate Number

Mark K. Schlüger
Training Director

Mark K. Schlüger

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Megan Vala

HAS SUCCESSFULLY COMPLETED A 16 HOUR COURSE ENTITLED

Asbestos Management Planner Initial

INCLUDING CLASSROOM INSTRUCTION

05/21/2015 to 05/22/2015

Exam passed on this 22nd day of May 2015 - Score - 94

Approved for AHERA Accreditation Under TSCA Title II

DIRECTOR:



James A. Welts, CIH, President

3370 Progress Drive, Suite J

Bensalem, PA 19020

(215) 244-1300 - Phone

(215) 244-4349 - Fax

www.criterionlabs.com

Course is conducted in English

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Management Planner Refresher

INCLUDING CLASSROOM INSTRUCTION


on this 5th day of April 2016

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:



James A. Welts, CIH, President

EMSL ANALYTICAL, INC.

Certifies that

Scott Magee

has successfully completed the course of study for the

Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II


EMSL Certificate No. 70016699C

Approved by:
PA Dept. of Labor and Industry
Accreditation # 137

Course Date: 8/15/2015
Granted: 8/15/2015
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077
Phone: (800) 220-3675
Fax: (856) 786-5973
www.emsl.com



Michael P. Menz
Michael P. Menz, CIH
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

EMSL ANALYTICAL, INC.

Certifies that

William Garrity

has successfully completed the course of study for the

Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II


EMSL Certificate No. 70016699A

Approved by:
PA Dept. of Labor and Industry
Accreditation # 137

Course Date: 8/15/2015
Granted: 8/15/2015
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077
Phone: (800) 220-3675
Fax: (856) 786-5973
www.emsl.com



Michael P. Menz

Michael P. Menz, CIH
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

45397

National Asbestos & Environmental Training Institute

CERTIFICATE OF COMPLETION

AHERA/EPA Accredited Per 40 CFR Part 763
Asbestos Accreditation under TSCA Title II

This is to certify that


Bernard Brunner, Jr.

Successfully completed the course entitled

**1/2-Day New York State/EPA/AHERA Asbestos Building Inspector Annual Refresher on
October 2, 2015**

Examination Passed October 2, 2015

Expiration Date on October 2, 2016


Doris I. Adler
President, NAEETI

Per 10 NYCRR Part 73.2 (L) (1), DOH 2832 Certificate of Completion of Asbestos
Safety Training is the only official record of training for N.Y.S. students.

Language: English

ABIH 1/2 CM POINT

3321 Doris Avenue, Building B, Ocean, NJ 07712

Phone (732) 531-5571

Fax (732) 531-5956

www.naeti.com

Number 740092

Expiration Date:
03/03/2016

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

on this 3rd day of March 2015

Exam passed on this 3rd day of March 2015 - Score - 84

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:


James A. Welch, CIH, President

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 5th day of April 2016


Exam passed on this 5th day of April 2016 - Score - 88

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:



James A. Weltz, CIH, President

Certificate of Completion

James Madden

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by
ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

12/11/14

Course Date

N/A

Exam Date

12/11/15


Expiration Date

Not Provided

Social Security Number

ACC-1214-6-010

Certificate Number


Mark K. Schlüger
Training Director

Certificate of Completion

James Madden

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

12/3/15

Course Date

N/A

Exam Date

12/3/16


Expiration Date

Not Provided

Social Security Number

ACC-1215-6-018

Certificate Number


Mark K. Schlüger
Training Director

Certificate of Completion

Troy A. Ray

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449


3/19/15
Course Date

N/A
Exam Date

3/19/16
Expiration Date

Not Provided
Social Security Number

ACC-0355-6-011
Certificate Number


Mark K. Schlager
Training Director

CERTIFICATE NO 374

G&C Environmental Services, Inc. (#294)
2 Street Road, Newtown Square, Pennsylvania 19073
Telephone: (610) 993-9202 Facsimile: (610) 993-9232
Email: Training@gcenviro.com
www.GCenviro.com

This document certifies that Ananth K. Vinjamuri has successfully completed this
State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.
MM DD YR MM DD YR

The examination date was 09/29/2015. This certificate expires one year from the date of
MM DD YR MM DD YR
successful completion of the examination 09/29/2016.
MM DD YR

*The official record of successful training completion is the New York State Department of
Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner
Training Director

Gail M. Conner

CERTIFICATE NO 375

G&C Environmental Services, Inc. (#294)
2 Street Road, Newtown Square, Pennsylvania 19073
Telephone: (610) 993-9202 Facsimile: (610) 993-9232
Email: Training@gcenviro.com
www.GCenviro.com

This document certifies that Shelton Williams has successfully completed this
State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.

The examination date was 09/29/2015. This certificate expires one year from the date of
successful completion of the examination 09/29/2016.

*The official record of successful training completion is the New York State Department of
Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner
Training Director

Gail M. Conner

Certificate of Completion

Paul M. Davis

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/12/15

Course Date

N/A

Exam Date

2/12/16


Expiration Date

Not Provided

Social Security Number

ACC-0215-6-015

Certificate Number


Mark K. Schlüger
Training Director

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Paul M. Davis

Asbestos Building Inspector Refresher

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

INCLUDING CLASSROOM INSTRUCTION

on this 2nd day of February 2016

Exam passed on this 2nd day of February 2016 - Score - 92

Approved for AHERA Accreditation Under ISCA Title II

DIRECTOR:

James A. Wertz, CIH, President

3370 Progress Drive, Suite J
Bensalem, PA 19020

(215) 244-1300 - Phone

(215) 244-4349 - Fax

www.criterionlabs.com

Course is conducted in English

Certificate of Completion

Bernard J. Bryson

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/16/15

Course Date

N/A

Exam Date

2/16/16

Expiration Date

Not Provided

Social Security Number

ACC-0125-6-031

Certificate Number

Mark K. Schlager
Training Director

Certificate of Completion

Bernard J. Bryson

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/15/16

Course Date

N/A

Exam Date

2/15/17

Expiration Date

Not Provided

Social Security Number

ACC-0216-6-005

Certificate Number

Mark K. Schlager
Mark K. Schlager
Training Director

EHS TRAINING INSTITUTE, INC.
A Division of BATA, Inc.

Certificate of Completion

AHERA Building Inspector (Refresher)

Awarded To:

Alexander Roman

SS#:XXX-XX-1743
Who has completed this 4-hour course and examination,
EPA Approved under TSCA Title II
AHERA / ASHARA Rule
40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATA, Inc.

Delaware Industrial Park • 6 Garfield Way
Newark, DE 19713-5817
(302) 737-3376 • Fax (302) 737-5764

Course Date: September 18, 2015

Date of Expiration: September 18, 201

Certification Number : EHSBIR 150619-008



Todd K. Zeisloff, Instructor



Neeraj K. Batta, President

Certificate of Completion


Norman Harrison

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by
ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08109
(856) 665-3449

9/2/15 <i>Course Date</i>	N/A <i>Exam Date</i>	9/2/16 <i>Expiration Date</i>
Not Provided <i>Social Security Number</i>	ACC-0915-6-011 <i>Certificate Number</i>	 Mark K. Schlager <i>Training Director</i>

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.


Certificate of Completion


AHERA Building Inspector (Refresher)

Awarded To:
Kelly Mayberry

Who has completed this 4-hour course and examination,
SS#:XXX-XX-1551
EPA Approved under TSCA Title II
AHERA / ASHARA Rule
40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.
Delaware Industrial Park • 6 Garfield Way
Newark, DE 19713-5817
(302) 737-3376 • Fax (302) 737-5764
Course Date: February 20, 2015
Date of Expiration: February 20, 2016
Certification Number : EHSBIR 150220-005


Todd K. Zeisloff, Instructor


Neeraj K. Batta, President

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.

Certificate of Completion

AHERA Building Inspector (Refresher)

Awarded To:

Kelly Mayberry

SS#:XXX-XX-1551
Who has completed this 4-hour course and examination,
EPA Approved under TSCA Title II
AHERA / ASHARA Rule
40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.
Delaware Industrial Park • 6 Garfield Way
Newark, DE 19713-5817
(302) 737-3376 • Fax (302) 737-5764

Course Date: February 18, 2016
Date of Expiration: February 18, 2017
Certification Number : EHSBIR 160218-006


Todd K. Zeisloff, Instructor


Neeraj K. Batta, President

AEROSOL MONITORING & ANALYSIS, INC.

This is to certify that
ANDREW HINE

has met the attendance requirements and successfully completed

the course entitled

3-DAY EPA AHERA INSPECTOR

For Accreditation Under TSCA Title II

05/04/2015 to 05/06/2015

Course Date

05/06/2015


Exam Date

5/6/2016

Expiration Date

STEVE STERAGKI

Principal Instructor




A105042015-3

Certification No.

E. Rush Barnett

Course Director



1331 Ashton Road

P.O.Box 646

Hanover, MD 21076

P: 410-684-3327

F: 410-684-3724

www.amatrainig.com

Certificate of Completion

Maryellen Leotta

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/12/15

Course Date

N/A

Exam Date

2/12/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-6-024

Certificate Number

Mark K. Schlager
Training Director



Section IV Cross Reference Table

Asbestos Hazard Emergency Response Act (AHERA) Environmental Compliance Audit Cross Reference Table

In response to the AHERA Environmental Compliance Audit a Cross Reference Table has been prepared for inclusion into the Environmental Management Plan. The purpose of this Cross Reference Table is to link the following documents to the AHERA Management Plan.

Cross Reference Table	
3 Year Reinspection Report follows this Cross Reference Table documentation.	
Subject Matter	Location of Required Documents
Designated Person	Pages 1 - 3
Annual Notification	Pages 4 - 5
6 Month Periodic Surveillance Outline of Events	Page 6
3 Year Re-inspections Outline of Events	Page 7
Asbestos Management Program (operations and maintenance)	Pages 8 - 19
Asbestos Investigation Report (AIR)	Attachment 1 Letter Dated August 4, 2006
Training (included in the Asbestos Management Program)	<p>The original records are centralized at the School District's Environmental Library. Copies are maintained on staff and are required to be maintained in the latest Reinspection Report.</p> <p>2 hour awareness training records for all Building Engineers, Custodian Assistants and maintenance personnel</p> <p>40 hour worker/supervisor training records for the OEMS A-Team and various AST tradesmen.</p>
Response Actions (monthly mailings if applicable)	<p>The original documents are on file at the School District's Environmental Library.</p> <p>Copies of the original are mailed to the Schools Main Office for retention with the Management Plan documentation. These documents are typically kept separate from the management plan in an update binder due to the potential volume of response action reports.</p>

SCHOOL DISTRICT OF PHILADELPHIA

ASBESTOS DESIGNATED PERSON

Gerald F Junod
Office of Capital Programs
Environmental Management & Services
440 N Broad Street, 3rd Floor
Philadelphia, PA 19130
Telephone: 215 400 6738
Fax: 215 400 4751

Drexel University- Asbestos Building Inspector Course January 9-11, 1989 24 Hours
Drexel University- Asbestos Management Planner Course January 12-13, 1989 16 Hours
Criterion Laboratories, Inc. - Asbestos Management Planner Course October 11-12, 2012 16 Hours

Annual Building Inspector Refreshers 1990 to Present
4 Hours
Drexel University
Criterion Laboratories, Inc
Access Training Services, Inc.

Annual Building Management Planner Refreshers 1990 to 1994
4 Hours
Drexel University
Criterion Laboratories, Inc 2013 to Present
4 Hours

Environmental Manager, School District of Philadelphia
Manages the design and implementation of asbestos and lead projects for the Capital Improvement Program and other District Departments including Facilities & Operations and Information Technology. Ensures that asbestos abatement and lead remediation projects are expertly designed and executed in accordance with industry best management practice standards and regulations.

Manager, City of Philadelphia Asbestos Control Program
Served as the Asbestos Control Program Manager for the City of Philadelphia, Department of Public Health, Air Management Services, Asbestos Control Unit from August 1, 2003 through October 23, 2006.

Mid Atlantic Regional Environmental Consortium (MAREC)
Former member with attendance and participation commitments of all quarterly EPA Region III and yearly National Asbestos Regulatory Conferences sponsored by the EPA and the National Conference of State Legislators respectively as a representative for the City of Philadelphia Department of Public Health Air Management Services from 1994 through 2006.


Philadelphia Environmental Task Force
Former member of the Philadelphia Environmental Task force as a representative and point of contact for the City of Philadelphia Department of Public Health Air Management Services Asbestos Control Unit from 2002 through 2006.

Asbestos Instructor

Worked as the primary instructor for the initial and annual Asbestos Project Inspector training and licensing program as mandated by City of Philadelphia Department of Public Health Asbestos Control Regulations from August 1994 through October 2006.

Worked as a lead instructor with an Environmental Consulting Firm and approved by the US EPA for the initial and annual refresher training courses for various asbestos occupational disciplines such as the Building Inspector, Management Planner and Worker/Supervisor from 1991 through 1994.

I certify that the general, local agency responsibilities as stipulated in Section 763.84 will be met.



**Gerald F. Junod
Asbestos Designated Person
Environmental Manager
Office of Environmental Management and Services**

SCHOOL DISTRICT OF PHILADELPHIA

Accreditation Information Statement

All persons who inspect for Asbestos Containing Building Materials (ACBM) and who will design or carry out response actions with respect to assumed and confirmed ACBM, will be accredited by an EPA approved course and/or a State Contractors Accreditation Program under Sections 206 (c) and 206 (b) of Title II of the ACT.



Gerald F. Junod
Asbestos Designated Person
Environmental Manager
Office of Environmental Management and Services

SCHOOL DISTRICT OF PHILADELPHIA
OFFICE OF CAPITAL PROGRAMS
440 NORTH BROAD STREET, SUITE 373
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

September 2015

TO: Principals
Building Administrators/Occupants
Parents/Guardians

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: Annual EPA Notification Letter


Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 C.F.R. 763.84 (c)(d) of public access to environmental records, this letter is to acknowledge the availability of your facility's Asbestos Hazard Emergency Response Act (AHERA) Management Plan.

Each member of the school staff, parents/guardians, temporary workers and/or contractors, are required to receive a copy of the Notification Letter. At the direction of the Principal, a copy is to be posted on the bulletin boards and an appropriate amount of copies are to be generated for distribution.


Note: The AHERA Three-Year Reinspection reports, in colored binders; White with Pink, Tan, Black, Red, Dark Blue, Green, Yellow and White, are Federal EPA mandated inspection documents. The School District of Philadelphia is subject to severe monetary penalties if the reports and associated paperwork are not available to the EPA and the public upon request.

It is incumbent on designated school personnel to gather and retain this data as it is delivered, in one location for future review. Acceptable locations include the Principal's Office or Main Office for the primary data. The Building Engineer should maintain any secondary or duplicate copies.

If you have any questions, please call 215-400-4750. Thank you for your cooperation.



Fran Burns
Chief Operating Officer



Francine Locke, M.S., Director
Office of Environmental Management
and Services

c: Danielle Floyd

AHERA-4
8/21/15



School District of Philadelphia
OFFICIAL NOTICE

PLEASE POST

September 2015

TO: Principals
Building Administrators
Building Engineers
Building Occupants
Parents/Guardians

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: Annual Notification Letter: Asbestos Hazard Emergency Response Act

The Federal Register published on October 30, 1987, Subpart E, in Schools: Final Rule and Notice, 763.84 (c)(d) states that each local education agency shall ensure that workers and building occupants or guardians are to be informed at least once each school year about inspections, response actions and post-response action activities including re-inspections and periodic surveillance activities. The School District as the Local Education Agency (LEA), retains such reports that are available for public inspection in the Office of the Principal or Building Administrator.

The Principal or Building Administrator is required to do the following with this notification:

- 1) Post in a Public Place or Main Office
- 2) Inform Building Occupants
- 3) Send a copy of this notification to Parents or Guardians
- 4) Insert a copy into the latest AHERA Three-Year Reinspection report (white/pink binder) in your office or facility.

Handwritten signature of Fran Burns in black ink.

Fran Burns
Chief Operating Officer

Handwritten signature of Francine Locke in black ink.

Francine Locke, M.S., Director
Office of Environmental Management
and Services

c: Danielle Floyd

AHERA-4a
8/21/15

SCHOOL DISTRICT OF PHILADELPHIA
Education Center
440 North Broad Street
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA
Six Month Surveillance
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.92(b), the following procedure is to be implemented. At least once every six (6) months after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a periodic surveillance in each building that it owns or leases that contains Asbestos Containing Building Materials (ACBM) or is assumed to contain ACBM.
- The first Bi-Annual Inspection starts in the Spring (March, April, May) and again in the Fall (October, November, December) of each year. The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspace/Attics) and rooms in the facility. There is no action required of the Principal.
- The Building Inspector shall visually inspect all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials.
- The Building Inspector shall make a copy of the inspection document and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.

SCHOOL DISTRICT OF PHILADELPHIA
Education Center
440 North Broad Street
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA
Three Year Reinspection
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.85(b) the following procedure is to be implemented. At least once every three (3) years after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a reinspection of each building that it owns or leases that contains Asbestos Containing Building Material's (ACBM's) or is assumed to contain ACBM.
- Subsequent Three Year Re-inspections (2009, 2012, 2015, etc) shall start in the Fall (October, November, December, January). The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspace/Attics) and rooms in the facility. There is no action required of the Principal.
- An accredited Building Inspector shall visually inspect and touch to determine friability, all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials. The Building Inspectors state of accreditation and license number is required.
- After the inspection, the Building Inspector shall make a copy of the inspection documents and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.
- The Building Inspector shall return the reinspection data to the Management Planner to be assessed and determine appropriate response actions and a report issued (AHERA Three Year Reinspection report). One copy of the report is delivered to the schools Principal to be permanently retained with all previous environmental data. Another copy is retained in the LEA's Environmental Library.



School District of Philadelphia
Office of Environmental Management & Services
440 North Broad Street
Philadelphia, PA 19130
(215) 400-4750

**School District of Philadelphia
Asbestos Management Program**

TABLE OF CONTENTS

Definitions.....	Page 9
1. Introduction.....	Page 10
2. Summary of Asbestos Management Plan	
3. Asbestos Management Plan Execution.....	Page 11
a. General Execution	
4. Summary of Program Execution	
a. Asbestos Management Plan Execution	
5. Responsibilities	
a. OEMS	
b. Asbestos Worker/Supervisor “A-TEAM”.....	Page 12
c. Asbestos Designated Person	
d. Supervisor or Project Manager (Capital, Maintenance & Facilities)	
e. Employee Capital.....	Page 13
f. Employee Maintenance	
g. Employee Facilities and Custodial	
6. Requirements.....	Page 14
a. Employee Exposure Monitoring	
b. Employee Notification	
c. Observation of Monitoring	
d. Training Program	
e. Access of Information	
f. Record Keeping	
7. AHERA O&M Plan.....	Page 15
a. Controls	
8. O&M Response Actions.....	Page 16
a. Facility Maintenance Isolation of Area	
b. Unlikely Contact with ACM/PACM	
c. Accidental Disturbance of ACM/PACM	
d. Planned Disturbance of ACM/PACM	
e. Miscellaneous ACM/PACM.....	Page 17
f. Vinyl Asbestos Floor Tile	
g. Mastic/Adhesives	
h. Woven Vibration Dampers	
i. Other Work Practices	
j. Fiber Release Episodes	
9. References and Resources.....	Page 18

DEFINITIONS / ACRONYMS

ACM/PACM:	Asbestos Containing Material/Potential Asbestos Containing Material
AHERA:	Asbestos Hazard Emergency Response Act
AIR FORM:	Asbestos Inspection Report Form
Amended Water:	Water to which a surfactant (soap) has been added
AMP:	Asbestos Management Program/Asbestos Management Plan
Asbestos Designate Person:	Individual assigned by the district to oversee asbestos related issues.
Asbestos Regulated Area:	Location that is posted as an asbestos work area in which only approved and accredited personnel are permitted to enter
AST:	Asbestos Support Team involving approved and accredited school district tradespersons personnel that are school district person
A-TEAM:	School District of Philadelphia asbestos workers
CIP:	Capital Improvement Program
Consultant:	Asbestos consulting firm hired by the District
Demolition Directive:	Memorandum – August 4, 2006 from Patrick Henwood
EPA:	Environmental Protection Agency
In House Personnel:	School District of Philadelphia asbestos workers
LEA:	Local Education Agency
O&M:	Operations and Maintenance
OEMS:	Office of Environmental Management and Services
OSHA:	Occupational Safety and Health Administration
PEL:	Permissible Exposure Limit
PSD or SDP:	Philadelphia School District/School District of Philadelphia
PSIT:	Philadelphia School Improvement Team
STEL:	Short Term Exposure Limit

1. Introduction

The School District of Philadelphia, Asbestos Policy Statement:

“The School District of Philadelphia is dedicated to providing a safe and healthful work environment for its employees, students, faculty, contractors and visitors. In recognition of the potential health problems associated with asbestos, the School District of Philadelphia is committed to a comprehensive asbestos control program. This program is implemented and maintained through the School District of Philadelphia's Office of Environmental Management and Services (OEMS).”

OEMS has the responsibility of establishing procedures for asbestos abatement, asbestos inspection, air monitoring, renovation and demolition activities within all School District of Philadelphia owned or leased facilities.

These procedures are developed to ensure that:

- (1) People are not exposed to significant levels of asbestos fibers
- (2) Asbestos waste is handled and disposed of properly
- (3) Members of the School District of Philadelphia community have access to the Office of Environmental Management and Services for information, assistance, guidance, and interpretation regarding asbestos related matters.
- (4) Members of the School District of Philadelphia community have access to the Asbestos Management Plans as required and outlined in the US EPA AHERA regulations including annual written notification to all parents.
- (5) Compliance with all applicable Federal, State and Local Asbestos Regulations

Requirements outlined in this manual are mandatory in nature where the word “SHALL” is used and are advisory in nature where the word “SHOULD” is used.

2. Summary of Asbestos Management Program

The School District of Philadelphia's Asbestos Management Program was established to meet the requirements of Federal, State, and Local Regulations.

These regulations include, but are not limited to:

- US Environmental Protection Agency Asbestos Hazard Emergency Response Act (US EPA AHERA) and National Emissions Standard for Hazardous Air Pollutants subpart M, Part 61 (NESHAP);
- US Department of Labor, Occupational Safety and Health Administration (OSHA) General Industry Standard (29 CFR 1910.1001) and the OSHA Asbestos Standard for the Construction Industry (29 CFR 1926.1101);
- The Commonwealth of Pennsylvania, Department of Labor and Industry, Asbestos Occupations, Accreditation and Certification Act;
- The City of Philadelphia, Department of Public Health, Asbestos Control Regulations.

3. Asbestos Management Program Execution

a) General Execution

The Office of Environmental Management and Services (OEMS) develops, implements and manages safety and health programs for the School District of Philadelphia faculty, staff and students and assists with ensuring that all contractors comply with Federal, State and Local Environmental Regulations. The OEMS provides the oversight of School District of Philadelphia employees (Asbestos A-Team), environmental consultants, and asbestos abatement contractors for all projects within the School District of Philadelphia concerning Asbestos Containing Materials.

The control of safety and health hazards at the School District of Philadelphia is primarily through the implementation of engineering, work practice and administrative controls. Personal Protective Equipment (PPE) is used to supplement these controls or whenever the controls are not feasible or are in the process of being implemented. PPE is also recommended whenever exposures to chemical, physical or biological agents can be prevented or reduced by its use.

This written program establishes the procedures necessary to:

- 1) meet established standards and federal regulations for occupational exposure to asbestos fibers;
- 2) meet the requirements of the City of Philadelphia Asbestos Control Regulations which encompasses the disturbance and/or abatement of asbestos containing building materials;
- 3) provide the necessary health and safety protection to the School District of Philadelphia staff, faculty, students, contractors and visitors.

This program is strengthened by input and cooperation with the Philadelphia Federation of Teachers (PFT), Health and Welfare Fund.

4. Summary of Program Execution

a) Asbestos Management Program Execution

The Asbestos Management Program is administered by the Office of Environmental Management and Services (OEMS). OEMS provides the following services primarily through professional consultants:

- (1) exposure monitoring services;
- (2) building inspection/surveys (bulk sampling) for the identification of asbestos containing materials;
- (3) asbestos project design services;
- (4) asbestos abatement project and air monitoring services;
- (5) emergency response to fiber release episodes;
- (6) education/information;
- (7) medical monitoring;
- (8) training for School District of Philadelphia personnel

5. Responsibilities

a) Office of Environmental Management and Services

OEMS is responsible for performing the following functions:

- (1) Developing and administering of the Asbestos Management Program.
- (2) Providing asbestos-related services to all School District of Philadelphia departments.
- (3) Conducting required training of the Asbestos Management Program and working jointly with departments to schedule training.
- (4) Identifying and posting areas where labeling/signage are required.
- (5) Medical Monitoring of OEMS "A-TEAM" and other departments "AST" Asbestos Program staff.

- (6) Certification and training as required for OEMS "A-TEAM" and other departments "AST" Asbestos program staff.
- (7) Record keeping as outlined in Section 3.5 and all records as by required by US EPA AHERA regulations.

b) Asbestos Worker/Supervisor - "A-TEAM"

- (1) OEMS shall ensure that all "A-TEAM" workers/supervisors adhere to the following requirements:
 - a) Attend an initial Worker/Supervisor Asbestos Course;
 - b) Maintain the annual re-certification per EPA AHERA requirements and Commonwealth of Pennsylvania Asbestos Occupations, Accreditation and Certifications Act;
 - c) Undergo an annual Asbestos Medical Evaluation;
 - d) Undergo an annual Respirator Medical Clearance;
 - e) Undergo an annual Respirator Fit Testing.

c) Asbestos Designated Person

The Asbestos Designated Person is responsible for:

- (1) Assuring the health and safety of employees, students and visitors in the School District of Philadelphia facilities under his/her control.
- (2) Being kept informed of all areas under his or her jurisdiction where potential asbestos exposures exist and initiating protection programs that adhere to the Asbestos Management Program requirements of this manual.
- (3) Assuring that Asbestos Management Program requirements are adhered to by principal investigators, project managers, supervisors, or division heads, and School District of Philadelphia personnel under their supervision.
- (4) Ensuring that all employees within the Asbestos Management Program comply with (OSHA 1910.1001 (j) (7) (iv)) and the US EPA AHERA regulations by attending the required training.
- (5) Ensure the posting of:
 - a) Warning labels/signage
 - b) Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification form
 - c) Asbestos Inspection Reports (AIR) form (where required)
 - d) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

d) Supervisor or Project Manager (Capital, Maintenance and Facilities)

Each person in charge of a project, maintenance/repair, renovation/demolition, or other activity from the Departments of Capital, Maintenance, and/or Facilities, where asbestos containing material may be present is responsible for:

Identifying, with the assistance of OEMS, asbestos containing building materials prior to any disturbance of these materials. Various Federal (EPA and OSHA) and Local (City of Philadelphia Asbestos Control Regulations) require Asbestos Inspections prior to renovation/demolition activities. This shall be accomplished by always following the Asbestos Management Program Procedures as follows:

- (1) Ensure that the requirements of the Asbestos Management Program Procedures are followed by all personnel, trades, and contractors who are involved with the project;

- (2) Review of the required Asbestos Inspection Report (AIR) form (Attachment 1) and AHERA Management Plan documents prior to activities that may disturb any Asbestos Containing Materials;
- (3) Perform all project related duties as outlined in the Project Management Responsibilities;
- (4) Keep the department chairperson or director informed on any actions proposed or taken regarding the Asbestos Management Plan;
- (5) Ensuring that Construction Projects follow the Demolition Directive procedure outlined in the August 4, 2006 letter.

e) Employee – Capital

School District of Philadelphia Capital employees and/or consultants shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of the projects they are performing or managing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit (a.k.a PSIT Service Request Form) and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode upon discovery of visible damage to asbestos containing materials.
- (3) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

The types of projects represented as part of the Capital Improvement Program are as follows:

- (1) Complete Renovation of an existing building that addresses all facility component concerns and educational program needs;
- (2) Major Renovation of an existing building addressing significant facility component and educational improvements;
- (3) Addition to an existing building (either as an attachment or stand-alone structure) to accommodate needed program space;
- (4) Conversion of an existing facility to accommodate a change in educational program;
- (5) Facility Component Improvement of specific facility needs (i.e. electrical or HVAC system upgrades, ADA improvements, life safety improvements, exterior renovations, etc.)

f) Employee – Maintenance

School District of Philadelphia Maintenance employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in maintenance activities shall attend required Asbestos Awareness training program within 60 days of employment.

g) Employee – Facilities & Custodial

School District of Philadelphia Facilities and Custodial employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed;
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in Facilities and Custodial activities shall attend require Asbestos Awareness training program within 60 days of employment.

6. Requirements

a) Employee Exposure Monitoring

When information indicates that an employee's exposure to asbestos fibers may equal or exceed an 8-hour time-weighted average of 0.1 f/cc * (per OSHA 1910.1001 & 1926.1101), OEMS shall develop and implement an asbestos exposure monitoring program. The sampling strategy shall be designed to identify employees by work task (job classification) that is exposed to asbestos fibers that exceed an 8-hour time-weighted average of 0.1 f/cc.

b) Employee Notification

OEMS shall notify in writing, each employee exposed to asbestos fibers at or above an 8-hour time weighted average of 0.1 f/cc.

c) Observation and Monitoring

OEMS shall provide employees or their representatives with an opportunity to observe any exposure measurements conducted.

d) Training Program

OEMS shall institute a training program which meets the requirements of AHERA for all employees who perform maintenance operations in a facility/school which contains asbestos containing materials or presumed asbestos containing materials and 1910.1001 (j), and the Commonwealth of Pennsylvania Department of Labor and Industry and the City of Philadelphia Asbestos Control Regulations. The affected departments shall ensure employee participation in this program. The OEMS "A-TEAM" and other departments "AST" Asbestos Program staff training shall be conducted annually for each employee as required by all Federal, State and Local for each asbestos discipline.

All Asbestos Awareness training as required by AHERA shall be performed within 60 days of employment and shall include:

- Health effects of asbestos
 - Locations of ACM and PACM in the building/facility
 - Recognition of CM and PACM damage and deterioration
 - Requirements of the OSHA 1910.1001 standard relating to maintenance
 - Proper response to fiber release episodes
 - Procedure to be followed to isolate areas affected by fiber release
- e) **Access to Information**
OEMS shall make available to affected employees or their representative's copies of the Occupational Safety and Health Administration (OSHA) General Industry Standard Part 1910.1001 and the department shall post a copy in the workplace.
- f) **Record Keeping**
OEMS shall maintain an accurate record of all employee exposure measurements. OEMS and/or the School District of Philadelphia Human Resources Department shall maintain records of employee medical monitoring program. OEMS shall maintain all employee training records. All records shall be provided upon request to employees, former employees, representatives designated by the individual employee.

7. AHERA OPERATIONS AND MAINTENANCE PLAN

a) CONTROLS

i. Work Order System

Minimizing disruption of ACM/PACM during maintenance and renovation activities is the primary goal and task encountered by OEMS. Operations and maintenance employees and contractors should be warned to avoid conducting any maintenance work which may disturb ACM/PACM. Initiating a work order system, where all work orders or requests are channeled through the Office of Environmental Management and Services (OEMS), will be the method used to control and minimize disruption of ACM/PACM.

Any work performed by in-house personnel or contractors that could or will impact ACM/PACM shall be coordinated by OEMS. A completed Asbestos Inspection Report Form (Attachment 1) shall be issued to in-house personnel and/or all contractors whose work could impact ACM/PACM. This form should accompany each contract issued to an outside contractor and posted on the jobsite.

All work order requests for maintenance and renovation activities in areas where ACM/PACM is suspected or known to be present are to be submitted to OEMS prior to proceeding with work. OEMS is responsible for reviewing asbestos survey records for information about the presence of ACM/PACM in the area where the work is to be performed. OEMS should physically inspect the area to ensure existing records reflect actual conditions. If no asbestos is present, a work order is not necessary and the planned actions can proceed. If ACM/PACM is found to be present in the area, OEMS will sign the work order application and obtain an approved and accredited asbestos contractor or assign OEMS "A-TEAM" to abate the ACM/PACM.

ii. Regulated Areas

The owner will identify and regulate all areas where airborne concentrations of ACM/PACM exceed the Permissible Exposure Limit (PEL)* (Per OSHA determined to be 0.1 f/cc) and/or short term exposure limit (STEL) (Per OSHA determined to be 0.1 f/cc), or there is reasonable possibility that the (PEL) and/or (STEL) may be exceeded. All ACM/PACM removal activities involving thermal system insulation ACM/PACM (Class I), surfacing ACM/PACM (Class I), and miscellaneous ACM/PACM such as floor tile, roofing, and siding mastic, etc. (Class II), and repair and maintenance operations where thermal system insulation and surfacing ACM/PACM is likely to be disturbed (Class III) will be performed in accordance with federal, state, and local regulations. All asbestos abatement work and activities will be designed and managed as asbestos regulated areas. These areas will be demarcated and labeled.

iii. Warning Signs

Warning signs shall be displayed at all approaches to each asbestos regulated area. The asbestos abatement contractor will provide OSHA warning signs in all regulated areas during removal, repair, and other maintenance activities. OEMS will provide AIRs to all contractors who must inform all employees and supervisors working in locations contiguous to asbestos regulated areas of the potential hazards and work practices required.

iv. Warning Labels

Warning labels and/or signage shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing asbestos fibers, or to their containers. Generally, the asbestos abatement contractor or OEMS A-Team personnel will provide all warning labels for ACM/PACM containment.

8. O & M RESPONSE ACTIONS

The Asbestos Management Program general O&M procedures are outlined in this section. Additional requirements specific to asbestos abatement activities are included in the Project Design documents for all Asbestos Abatement Work. Regular cleaning, inspection, and reporting of ACM/PACM deterioration or other problems must be diligently practiced by all employees including custodial and maintenance personnel.

a) Facility Maintenance Isolation of Area Responsibilities

Maintenance personnel are often required to work in areas where ACM/PACM may potentially be disturbed. Most maintenance activities are conducted by in-house staff, outside contractors, or a combination.

Emergency fiber release episodes, such as pipe fitting or valve breaks, emergency boiler work, or mechanical equipment repair will be responded to by OEMS A-Team personnel or asbestos abatement contractor personnel. The owner's maintenance staff will: (1) isolate the emergency fiber release area; (2) post warning signs to prevent unauthorized access, and (3) notify their supervisor and OEMS. OEMS will ensure that the fiber release area remains isolated and is properly cleaned by and approved and accredited abatement contractor or by OEMS A-TEAM personnel.

b) Unlikely Contact with ACM/PACM

Maintenance activities or repairs which can be performed without contacting or disturbing the ACM/PACM require little more than normal care and good workmanship. For example, valves which are either uncovered or covered with non-asbestos insulation can be packed or repaired without disturbing asbestos insulation on nearby pipes. The major precaution is to ensure that maintenance and custodial personnel are familiar with procedures such as isolating the area, posting warning signs, and notifying OEMS in the event of any accidental ACM/PACM disturbance.

c) Accidental Disturbance of ACM/PACM

Maintenance and facilities personnel shall notify OEMS any time a fiber release is suspected. If friable ACM/PACM becomes airborne in the building,

d) Planned Disturbance of ACM/PACM

Maintenance activities that may impact ACM/PACM include access to a valve, flange, duct, or related system component.

Where asbestos-containing insulation must be removed to maintain or repair the thermal system, the ACM/PACM will imminently be disturbed. ACM/PACM removal work shall be conducted by OEMS A-Team personnel or an approved and accredited asbestos abatement contractor.

If friable ACM/PACM becomes airborne in the building, maintenance and facilities personnel shall secure the area and contact OEMS. OEMS shall respond accordingly.

e) Miscellaneous ACM/PACM

Miscellaneous types of ACM/PACM may include vinyl asbestos floor tiles, mastics/adhesives and woven vibration dampers. Disturbance of these materials should be avoided. Routine maintenance activities involving these materials should not pose a problem if handled properly. Questions on the proper removal and disposal of miscellaneous ACM/PACM should be directed to OEMS. OEMS will contact an approved and accredited asbestos abatement contractor or utilize OEMS A-TEAM personnel to assist with miscellaneous ACM/PACM clean-up activities.

f) Vinyl Asbestos Floor Tile

Asbestos-containing floor tiles in good condition are considered non-friable unless they are crushed, drilled, sawed, sanded or disturbed by any activity that breaks up the material. Routine maintenance of these materials should employ the use of non-abrasive buffers and wet cleaning technique. Broken or loose floor tiles should be removed and disposed of as asbestos waste by OEMS. Remaining debris should be vacuumed with a HEPA vacuum and the area wet mopped using amended water.

g) Mastics/Adhesives

Mastics and adhesives containing asbestos in good condition are considered non-friable and do not pose a potential health concern unless crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

h) Woven Vibration Dampers

Woven vibration dampers in good condition are considered non-friable and do not pose a potential health concern unless cut, crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

i) Other Work Practices

Any special work not included in this section should be addressed to OEMS for review prior to the initiation of work that may involve the disturbance of ACM/PACM.

j) Fiber Release Episodes

Facilities and maintenance staff should report to OEMS the presence of asbestos debris, water or physical damage to ACM/PACM, or any other evidence of possible fiber release. OEMS should have the OEMS A-Team personnel or an approved and accredited abatement contractor respond to the site to clean up debris and make repairs as soon as possible. OEMS will also contact a consultant to conduct air monitoring and prepare a report and submit at project completion to OEMS for each episode. OEMS will forward the reports for each site location AHERA Management Plan accordingly.

9. REFERENCES and RESOURCES

Applicable regulations for asbestos projects impacted by renovation, demolition, and maintenance activities.

- **Philadelphia Air Management Services – Asbestos Control Unit**
<http://www.phila.gov/health/units/ams/Asbestos/asbestos.html>
- **Pennsylvania Asbestos Occupations, Accreditation and Certification Act**
<http://www.dli.state.pa.us/landi/cwp/view.asp?a=185&q=56262&landiNav=>
- **United States Environmental Protection Agency Asbestos Home Page**
<http://www.epa.gov/asbestos/>
- **Occupational Safety and Health Administration (OSHA) Asbestos Home**
<http://www.osha.gov/SLTC/asbestos>